

**Appendix B South West Herts Plan – Schemes Delivered in 2010 / 2011**

ACCESSIBILITY					
Scheme	Locations	Town	Date of Delivery	Before	After
College Road pedestrian crossing	College Road	Leavesden	Summer 2010	<u>June 09 – Ped &amp; Cycle Counts:</u> <ul style="list-style-type: none"> <li>▪ Friday: 66 peds &amp; 7 cyclists</li> <li>▪ Sunday: 55 peds &amp; 13 cyclists</li> </ul> <i>(Taken weekday &amp; weekend due to proximity of Leavesden Park)</i>	Before and After study to take place early in 2011/2012
<b>C76 Ovaltine Scheme</b> <ul style="list-style-type: none"> <li>▪ Resurfacing of significant sections of the carriageway between Kings Langley Rail Station and the Hyde Lane Railway bridge.</li> <li>▪ Drainage works around Hyde Lane railway bridge.</li> <li>▪ New footway in railway bridge by Hyde Lane.</li> <li>▪ Installation of traffic lights either side of railway bridge so that traffic will flow in one direction at a time through the bridge.</li> <li>▪ Installation of a new traffic island and bus stop improvement works in Railway Terrace near Lakeview.</li> <li>▪ Road markings in Lower Road.</li> <li>▪ Works in Station Road to provide part footway parking and installation of footway bollards in Primrose Hill.</li> <li>▪ New puffin crossing near Kings Langley railway station.</li> <li>▪ New pedestrian refuge island on Home Park Mill Link Road</li> </ul>		Kings Langley	Summer 2010	Awaiting results of the before and after survey.	

**Appendix B South West Herts Plan – Schemes Delivered in 2010 / 2011**

<b>QUALITY OF LIFE</b>					
<b>Scheme</b>	<b>Locations</b>	<b>Town</b>	<b>Date of delivery</b>	<b>Before</b>	<b>After</b>
Sydney Road 20mph Zone	Sydney Road	Watford	January 2011 <i>(some remedial works to be complete by end of March 2011)</i>	<u>March / April 09 – 85<sup>th</sup> %ile Spds:</u> <ul style="list-style-type: none"> <li>▪ o/s No. 2: 26.4mph / 33.7mph</li> <li>▪ o/s 50 – 28mph / 33.2mph</li> <li>▪ o/s 102 – 19.2mph / 24.5mph</li> </ul>	After counts to take place early in 2011-2012.
<b>MODE SHARE TO SCHOOL</b>					
<b>Scheme</b>	<b>Locations</b>	<b>Town</b>	<b>Date of delivery</b>	<b>Before</b>	<b>After</b>
Croxley Green Safe Routes to School Small Works Pilot	Yorke Mead Scool	Croxley Green	March 2011	<ul style="list-style-type: none"> <li>▪ 83% of pupils live within 1 mile of the school</li> <li>▪ 64% of pupils currently travel to school by sustainable modes.</li> </ul>	After counts taking place in 2011-2012.
<b>CYCLING</b>					
<b>Scheme</b>	<b>Locations</b>	<b>Town</b>	<b>Date of delivery</b>	<b>Before</b>	<b>After</b>
Watford Town Hall Cycle Link Phase 2	Sydney Road	Watford	Summer 2010	<u>West of Cassiobury Drive</u> <u>12 hour weekday count:</u> <ul style="list-style-type: none"> <li>▪ Pedestrians – 9, 508</li> <li>▪ Cyclists – 850</li> </ul>	After counts taking place in March 2011.
Oxhey Park Bridge (WBC scheme)	Oxhey Park	Watford	Summer 2010	Watford Borough Council scheme	
Cowarch Cycle Link	Bridleway between Prestwick Road & Delta Gain.	South Oxhey	April 2010	No counts taken	n/a

**Appendix B South West Herts Plan – Schemes Delivered in 2010 / 2011**

<b>CONGESTION</b>					
<b>Scheme</b>	<b>Locations</b>	<b>Town</b>	<b>Date of delivery</b>	<b>Before</b>	<b>After</b>
Travelsmart	Croxley Green	Croxley Green	July 2010 – June 2011	Results from the Travelsmart Croxley Green project will be made available in the final report due in June 2011.	
Variable Message Signage Installation	Various locations near and on boundary of town centre	Watford	March 2011	n/a	n/a
<b>SAFETY</b>					
<b>Scheme</b>	<b>Locations</b>	<b>Town</b>	<b>Date of delivery</b>	<b>Before</b>	<b>After</b>
A4008 Stephenson Way	Stephenson Way	Watford	October 2010	<u>January 2005 – December 2007:</u> <ul style="list-style-type: none"> <li>▪ 10 accidents</li> <li>▪ 1 serious injuries</li> <li>▪ 9 slight injuries</li> </ul>	After counts taking place in March 2011.
A411 Beechen Grove	Beechen Grove	Watford	October 2010	<u>January 2005 – December 2007:</u> <ul style="list-style-type: none"> <li>▪ 15 accidents</li> <li>▪ 3 serious injuries</li> <li>▪ 22 slight injuries</li> </ul>	After counts taking place in March 2011.
A405 Dome Roundabout Signals	Dome Roundabout	Watford	April 2010	<u>September 2005 – August 2008:</u> <ul style="list-style-type: none"> <li>▪ 31 accidents</li> <li>▪ 3 serious injuries</li> <li>▪ 28 slight injuries</li> </ul>	After counts taking place in March 2011.
Town Hall Roundabout	Hempstead Road	Watford	July 2010	<u>January 2004 – December 2006:</u> <ul style="list-style-type: none"> <li>▪ 27 accidents</li> <li>▪ 4 serious injuries</li> <li>▪ 23 slight injuries</li> </ul>	After counts taking place in March 2011.